



# ***Concrete Assessment and Service Life Extension (CAASLE AMENDMENT No. 3)***

***Presented by  
Mike McClendon  
Chief Projects Officer***



## **Concrete Assessment and Service Life Extension Phase III (Amendment No. 3)**

**Project Budget: \$460,000**


**Budget year approved: FY 26**

**Strategic Plan Goal:** *Section II b. Ensure the operation and maintenance of BRA water supplies and associated infrastructure in a safe, responsible manner in compliance with all applicable requirements.*



**Table 1-3: Summary of Higher-Risk Potential Failure Modes Identified in 2019 SQRA**

PFM Number	PFM Title	Likelihood	Consequence	Confidence
N-2	Bulkhead Deck Slab Failure due to Structural Concrete Deterioration during Normal Operations	Moderate	Level 4	Medium
N-3	Spillway Deck Slab Failure due to Structural Concrete Deterioration during Normal Operations	Moderate	Level 4	Medium
N-4	Upstream Bulkhead Corbel Failure due to Structural Concrete Deterioration during Normal Operations	High	Level 4	Poor
N-5	Upstream Spillway Corbel Failure due to Structural Concrete Deterioration during Normal Operations	High	Level 4	Poor
H-1	Upstream Deck Slab Failure due to Structural Inadequacy during Hydrologic Event	Moderate	Level 4	Medium
H-2	Upstream Corbel Failure due to Structural Inadequacy during Hydrologic Event	Moderate	Level 4	Poor
H-8	Downstream Spillway Slab Failure due to Structural Concrete Deterioration during Hydrologic Event	Moderate	Level 4	Medium
S-3	Corbel Failure due to Structural Inadequacy caused by Seismic Event	High	Level 4	Poor





# CAASLE Amendment No. 3


Morris Sheppard Dam CAASLE  
Phase III Long-Term Structural Concrete Testing & Repair Program

May 12, 2023

## MORRIS SHEPPARD DAM

CONCRETE ASSESSMENT AND SERVICE LIFE EXTENSION (CAASLE)

Phase III Long-Term Structural Concrete Testing & Repair Program  
Palo Pinto County, Texas  
May 12, 2023  
GF Job No.: 068993 | BRA RFP No.: 15-09-898



**Table 2-1: Priority Levels of Structural Features**

Feature	Priority Level
Upstream Slabs	High
Upstream Corbels	High
Crest Slabs	Medium
Crest Slab Corbels	Medium
Buttresses	Medium
Apron Slabs	Low
Cross-Canyon Stiffener Beams	Low
Downstream Corbel	Low





# CAASLE Amendment No. 3




Figure 3-1: Investigation and Repair Guide Flowchart



# Amendment Number 3

Phase III PSA NTE:	\$765,178
Amend. No. 1:	\$ 60,000
Amend. No. 2:	<u>\$300,000</u>
	\$1,125,178
<b>Proposed Amend. No. 3</b>	<b><u>\$460,000</u></b>
<b>New Phase III PSA NTE:</b>	<b>\$1,585,178</b>



Bay 31 Buttress 31 Corbel Repair





## Example of Concrete Repairs





**“BE IT RESOLVED** that the Board of Directors of the Brazos River Authority hereby authorizes the General Manager/CEO to execute Amendment Number 3 to the Professional Services Agreement with Gannett Fleming TranSystems Inc. for Phase III of the Concrete Assessment and Service Life Extension project increasing the total not to exceed amount by \$460,000.”



Brazos River Authority



**Brazos**


— ★ —  
**RIVER AUTHORITY**




# CAASLE Amendment No. 2

## OBSERVATION

### SLABS




A. Flexural Failure




C. Shear - Tension Failure



Flexural Cracking Example



B. Diagonal Tension Failure




D. Shear - Compression Failure




Shear/Tension Cracking Example


### CORBELS



A. Flexural Failure



B. Diagonal Tension Failure



C. Direct Shear Failure



Cracking Example

## EVALUATION

**1** Does reinforcing within the area of interest match record drawings?


Reference: APPENDIX E

Typical Upstream (Deck) Slab Record Drawing Reinforcement (Flexural)

Panel Info			Record Drawing Deck Panel Rebar Information		
Number	Upper Elevation	Lower Elevation	Rebar Size	Rebar Spacing (in.)	Number of Layers
1	1015	1005	8	5.00	1
2	1005	993	10	5.25	1
3	993	981	10	4.50	1
4	981	969	10	4.00	1
5	969	957	10	3.75	1
6	957	945	10	7.00	2
7	945	933	10	6.75	2
8	933	921	10	6.50	2
9	921	909	10	6.25	2
10	909	897	10	6.00	2
11	897	885	10	5.50	2
12	885	873	10	5.25	2
13	873	861	10	5.00	2
14	861	849	10	4.75	2
15	849	837	10	4.50	2
16	837	825	10	4.25	2
17	825	813	10	4.00	2

**2** Do the typical repair details apply to the deterioration condition?

Reference: APPENDIX E



**3** Does the deterioration level "Pass" the PFMSA tables?

Reference: Failure Mode Progression Structural Analyses, August 2022

Bulkhead Slabs - PMF Loading Conditions - Flexural DCRs

Slab Number	Elevation (ft) Center of Slab	Percentage of Reinforcement Remaining <sup>1</sup>									
		10%	20%	30%	40%	50%	60%	70%	80%	90%	100%
2	1010	2.41	1.21	0.81	0.61	0.49	0.41	0.36	0.32	0.28	0.26
3	999	3.24	1.63	1.09	0.83	0.67	0.56	0.48	0.42	0.38	0.34
4	987	3.54	1.78	1.19	0.90	0.72	0.61	0.52	0.46	0.41	0.37
5	975	3.65	1.83	1.23	0.93	0.75	0.63	0.54	0.47	0.42	0.38
6	963	3.77	1.89	1.27	0.96	0.77	0.65	0.56	0.49	0.44	0.40
7	951	4.00	2.01	1.35	1.02	0.82	0.69	0.59	0.52	0.47	0.42
8	939	3.79	1.91	1.28	0.96	0.78	0.65	0.56	0.49	0.44	0.40
9	927	3.84	1.93	1.29	0.98	0.79	0.66	0.57	0.50	0.45	0.40
10	915	4.02	2.02	1.35	1.02	0.82	0.69	0.59	0.52	0.47	0.42
11	903	4.31	2.17	1.45	1.10	0.88	0.74	0.64	0.56	0.50	0.45
12	891	4.32	2.17	1.45	1.10	0.89	0.74	0.64	0.56	0.50	0.46
13	879	4.47	2.25	1.51	1.14	0.92	0.77	0.66	0.58	0.52	0.47
14	867 <sup>2</sup>	4.79	2.41	1.61	1.22	0.98	0.82	0.71	0.62	0.56	0.50
15	855 <sup>2</sup>	4.84	2.43	1.63	1.23	0.99	0.83	0.72	0.63	0.56	0.51
16	843 <sup>2</sup>	4.87	2.45	1.64	1.24	1.00	0.84	0.72	0.63	0.57	0.51
17	831 <sup>2</sup>	5.12	2.58	1.73	1.30	1.05	0.88	0.76	0.67	0.60	0.54



# Pier Plate Wall Repairs






# Concrete Assessment And Service Life Extension Project

## CAASLE Budget/Schedule

Location	Project	CIP/OP	Estimated Cost	FY 21	FY 22	FY23	FY 24	FY 25	FY26	FY 27	FY 28	FY 29	FY 30-35
PK	CAASLE Phase III	OP	\$1,125,178										
Assessment Design				\$825,000			\$300,000		\$300,000				
Construction													

### Schedule/Status



### BRA's Strategic Plan

*In accordance with BRA's Strategic Plan: Section II b. Ensure the operation and maintenance of BRA water supplies and associated infrastructure in a safe, responsible manner in compliance with all applicable requirements.*