

19'-0"
2"X2"X11 GA. SPACED MAX. 16" O.C.

30'-0"
5'-0" 5'-0" 5'-0" 5'-0" 5'-0"

FLOAT FLOAT FLOAT FLOAT FLOAT FLOAT FLOAT FLOAT

6"X9# WF I-BEAM.

6"X9# WF I-BEAM.

2"X2" 11 GAUGE

1/2" CABLE ANCHOR TIE DOWN
9,000 # SEA ANCHOR

HINGE CONNECTION

4' WIDE HINGED WALKWAY

40'

BACK-TO-BACK 6" C-CHANNEL

1/2" CABLE ANCHOR TIE DOWN
9,000 # SEA ANCHOR


PIPE H-BRACE

STATIONARY WALKWAY

34'

NOTES:

1. DOCK FRAME TO BE 6"X9# WF I-BEAM.
2. DECK TO BE 2X6 TRIX COMPOSITE DECKING.
3. DOCK IS TO BE ANCHORED WITH TWO 9,000 POUND SEA ANCHORS
4. ALL STEEL TO BE GALVANIZED.
5. FLOATION PROVIDED BY 4'X6'X20" FLOATS.
6. ORIGINAL SCALE: 1/4" = 1'-0"



LIBERTY & HADA
1971 FM 574 W., MULLIN, TEXAS 76864
ENGR FIRM # F-9311
hadaengr@centex.net / 325-451-0223

MAY 20, 2025

JOB NO. 25033

CONTRACTOR:
LALKE VIEW DOCKS
845 MILSAP HIGHWAY
MINERAL WELLS, TEXAS 76067

GOLDEN COVE
POSSUM KINGDOM LAKE